OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Notification dated 2nd November 1936.

1. Sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, Mysore, up to 12 NOON on 16th November 1936, for Deviation of the T.-Narsipur Road near Lalithamahal, Mysore.

2. Tenders in the prescribed form obtainable from the Office of the Assistant Engineer, Headquarter Range, Mysore, on payment of rupee one for each form should be addressed to the Assistant Engineer, Headquarter Range, and should be superscribed as "Tender for the Deviation of the T.-Narsipur Road near Lalitha Mahal at Mysore." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 250 (Two hundred and fifty rupees only) in cash or Government Promissory Notes or Mysore Government Bonds at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. (Cash amount will not carry any interest).

4. The tenders will be opened in the presence of such tenderers who wish to be present on 16th November 1936 at 3 P.M. The final acceptance of the tender will rest with the Assistant Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever, for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Assistant Engineer's Office, in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings, may be seen at any time at the Office of the Assistant Engineer, Headquarter Range, Mysore, on all working days between 11 A.M. and 5 P.M.

8. Specific rate should be given for each item in the schedule and the rates should be in rupees, annas and in multiples of three pies and expressed in words and figures. Tenderers offering a percentage increase or decrease on the estimate amount or estimated rates or the lowest tender will be rejected.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the Contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a Firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney, authorising him to do so.

14. When once the rates tendered have been accepted they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Assistant Engineer, Headquarter Range, Mysore, and approved by the Superintending Engineer, shall be final and legally binding on the tenderer.

15. The quantities given in the schedule are only approximate, and are liable to alterations, omissions, deductions or additions, at the discretion of the Assistant Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

16. The work should be completed and handed over to the Public Works Department within five months from the date from which the work is ordered to be commenced, failing which the Assistant Engineer may, at his discretion, levy a penalty of Rs. 5 per day, which will be recovered from the Contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer, shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on submission of the receipts originally granted, along with an application, to the Assistant Engineer, Headquarter Range, Mysore.

19. No claims for damages, for delays caused by Officers of the Department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will however be considered on the merits of each case.

20. The Contract should not be sublet.

21. All materials, tools and plant and machinery, old doors, windows, etc., that will be supplied by the Assistant Engineer, in the interest of the work shall be accepted by the tenderer at the rates fixed by the Assistant Engineer, and the tenderers will pay the hire, etc., on machinery and tools and plant at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores. The dates considered being, the dates of acknowledgments of the vouchers in each transaction.

22. The Contractors should arrange for the payment of Royalty and Tolls.

Note (*A*).—The Contractor should at his own cost—

(1) Provide rods, stakes, ropes and labours required in setting out the works.
(2) Provide all necessary scaffolding, centering labour and appliance for hoisting.
(3) Provide mortar mill and shed to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water-shoots, coverings to masonry tile pieces to steps, sieves, parahs, or measures shoring and other requisite protection during the progress of the work.
(6) Supply all water required for work and workmen and shall provide latrines, drainages, etc.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and bailing from excavations, and foundations, wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.
(9) Wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, etc.
(10) Afford facilities to any other parties employed upon the work, so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

Note (*B*).—It is the business of the Contractor to make his own arrangements for the quarries and supplies of materials.

Approximate quantities for the proposed new deviation of the T.-Narsipur Road near Lalitha-mahal, Mysore.

No.	Items of work	Unit	Rate	Quantity
			Rs. a. p.	
1	Removing top soil	Cyds.	..	385
2	Excavating hard gravel and using for bank from C. S. "O" to junction with old Road	,,	..	1,681
3	Hard rock by blasting (mixed with soft rock)	,,	..	105
4	Earthwork embankment including carting spreading and consolidation	,,	..	712
5	Burnt stones including rounding and fixing	R.ft.	..	..
(*a*)	Guard stone 3′ × 1½′ do	Each	..	..
6	*Irish drain* :—			
1	Rough stone side walls paving, etc., complete	C.yds.	..	..
2	Brick in mortar side walls	C.ft.	..	..
3	Wheel track slabs 2′ wide roughly dressed and fixed on concrete bed	S.ft.	..	..
4	Chunam plastering	Sqr.	..	..
5	Pointing pavement with cement concrete and plastering	,,	..	..
6	Burnt stone slabs 6″ thick neatly dressed including fixing	S.ft.	..	..
7	Diverting the water course in voni	L. S.	..	..
8	Excavating side drains and using the same for road in cutting	C.yds.	..	315
9	Excavating shoulder drains	,,	..	208
10	Excavating check drains on the upper side	,,	..	587
11	Removing of hedging and rooting out trees along the alignment	Fur.	..	..
12	Providing stone finger post as per design of reinforced cement concrete	Each	..	..
13	Removing and refixing in altered positions the old furlong stones	L. S.	..	..

No.	Items of work	Unit	Rate	Quantity
	Mettalling the Road.		Rs. a. p.	
1	Collecting and stacking 4" rough metal for soling ..	C.yds.	..	367
2	Collecting, breaking, carting and stacking quartz metal $1\frac{1}{2}$" thick including lead	,,	..	367
3	Picking and forming road before spreading metal ..	,,	..	3,300
4	Spreading rough metal including hand packing to bring the road to shape	,,	..	367
5	Spreading quartz metal	,,	..	367
6	Consolidating rough and quartz metal with steam or petrol road roller including water charges	,,	..	734
7	Do with ordinary roller do ..	,,	..	..
8	Collecting and stacking gravel with lead and without making unsightly pits	,,	..	92
9	Spreading and consolidating gravel	,,	..	92
10	Collecting and spreading sand	,,	..	25

S. RAMASWAMY,
Assistant Engineer.

GOVERNMENT OF MYSORE, STORES PURCHASE COMMITTEE, BANGALORE.

No. S. P. C. 9038 *dated* 31*st October* 1936.

To

The Firms dealing in Machinery.

Enquiry No. 2020.

TURGO IMPULSE HYDRAULIC TURBINE REQUIRED FOR THE COLLEGE OF ENGINEERING, BANGALORE.

DEAR SIR/GENTLEMEN,

Please be good enough to intimate your best prices and the earliest time of delivery for the materials described in the attached schedule, in the form printed below.

It should be distinctly understood that the acceptance by us of your quotation will be subject to the following conditions:—

Withdrawal from the quotation after it is accepted or failure to make the supply within the specified time or according to specifications will entail cancellations of the order and purchases being made at your expense from other sources in addition to the levy of a penalty of 3 per cent of the value of the order as and by way of liquidated damages. In such an event, the Stores Purchase Committee reserve the right to remove your name from the list of approved firms.

The quotations should be superscribed "Quotations for Turgo Impulse Hydraulic Turbine required for the College of Engineering" with the above enquiry number.

This enquiry will be closed on the 15th December 1936.

Schedule.

Item No.	Description of material offered	Quantity	Price quoted F. O. R.	Time of delivery
	6 "Turgo" Impulse Hydraulic Turbine output 13.6 B.H.P. at 250 feet head and 250 gals. per min. Normal speed 2140 R.P.M. and maximum runaway speed 3,850 R.P.M. Runner of cast iron made in one piece and enclosed in strong cast iron casing. Casing to be split horizontally. Steel shaft carried in two roller bearings. Spear regulating nozzle with 4" diameter inlet branch, the nozzle piece and spear head being of gun metal. The spear rod to have outside screw with bronze nut and cast iron hand wheel. No coupling or belt pulley to be provided, but shaft arranged to take up a belt pulley.	One	Bangalore.	